

NOTICE TO BIDDERS

The Board of Supervisors of Tazewell County, Virginia is currently accepting sealed bids from qualified contractors to perform asphalt overlay paving with Bituminous Asphalt (Plant Mix) on various roads in Tazewell County.

GENERAL INFORMATION

- I. A **responsible** bidder shall:
 1. Provide proof that they are a licensed contractor in the Commonwealth of Virginia
 2. Provide proof of liability insurance in the amount of \$1 Million Dollars
 3. Pledge that they are in compliance with all workers compensation laws of the Commonwealth of Virginia
 4. Provide a list of equipment available for -use on this project
 5. Provide proof of bidder's corporate status where applicable.

- II. A **responsive** bid will state the price for the materials and labor for performing the improvements indicated on the attached bid sheets for each lot, based on the length, width, and estimated tonnage indicated.

ACKNOWLEDGEMENT BY BIDDER

Bidder acknowledges that the following will be incorporated by reference into the Contract awarded.

1. A contract will be awarded for each lot
2. Bidder assumes the responsibility of locating the road to be improved and incorporating any mobilization costs related to the bid
3. Bidder will proceed with the project within 10 days of the Notice to Proceed
4. The County reserves the right to reject any and or all bids
5. Bidder will submit an invoice to the county upon completion of each lot. The county will pay for work after completion in accordance with the Prompt Payment Act
6. The roads have been marked for paving and if the bidder cannot find the markings it is the bidder's responsibility to contact the Engineering Department to Verify the locations
7. Tazewell County will not pay for any work that does not have written authorization from the- County Administrator or his designee
8. Completion of work shall be finished no later than **September 8, 2026**. Failure to meet this deadline will result in liquidated damages of \$100 per day per uncompleted lot.

I have read and understand the proceeding Bid Qualifications. I agree that any contract I am awarded for this project will be subject to these terms.

Contractor

FIELD NARRATIVE

This project shall consist of furnishing and placement of Bituminous Asphalt (Plant Mix) overlay pavement on existing roadways and milling surfaces in accordance with the requirements of the Current Virginia Department of Transportation Road and Bridge Specifications and in reasonably close conformity with the lines, grades, and thickness as established by the schedule of work shown in the contract or as directed by the Engineer.

Traffic control is to be in accordance with the current Virginia Work Area Protection Manual.

TECHNICAL INFORMATION

1. Paved roads call for the application of one and one-half inches (1½") of compacted Bituminous Asphalt (Plant Mix) Overlay, unless otherwise noted
2. Gravel roads call for the application of 2-inch (2") of compacted Bituminous Asphalt (plant mix) Overlay unless otherwise noted
3. Measurements for the road shall be taken from edge of road surface to edge of road surface average widths are shown on provided lot descriptions and maps
4. Type of asphalt - SM-9.5AL
5. Milling must be done at all joints/transitions and paved driveways
6. Adequate crown shall be provided to allow for proper drainage
7. Tonnage tickets with the following information shall be provided to the Tazewell County Director of Engineering or his designee for each load of material used
 - Signature of Certified Weight Person
 - Date
 - Truck Number
 - Load Number
 - Plant Name
 - Size and Type of Material
8. The project manager shall be responsible for reconciling copies of tonnage tickets with those provided to the Tazewell County Director of Engineering or designee at the completion of each road
9. Siltation control measures shall be applied to erodible material exposed by any activity associated with construction, including clearing or grubbing, but not

limited to local materials sources, stockpiles, disposal area, and haul roads and shall be functional before land-disturbing activities take place

10. Lot 1 Pipe Replacement:

- Remove Existing Pipe
- Replace with a new corrugated metal (or comparable material) pipe that matches the diameter of the existing pipe
- Cover new pipe a minimum of 12" using combination of #1 stone and 21b stone with a minimum of 4" of 21b's
- Armor as needed
- See lot below for paving specifications
- Bidder must bid on both (as shown in lot 1) to be considered for this lot

11. Milling material must be removed from site and taken to a disposal area. The contractor is responsible for securing a disposal area. Millings may be brought to the Tazewell County Landfill.

Following is a list of each street for which bids are sought where a length and average width for roads for varying widths. It is the contractor's responsibility to verify the widths. All measurements are to be taken from edge of road surface to edge of. The bids should incorporate the following:

Bidder shall submit a price per ton applied for each lot. Bidder shall tabulate and submit a total price for each lot.

Tazewell County reserves the right to remove roads from lots.

All questions must be submitted in writing, preferably email, by 6 June 2025. All answers will be provided to the attendees of the pre-bid meeting.

Lot 1

ROAD	AVERAGE L x W (FEET)	ESTIMATED TONS	BID PRICE	PRICE PER TON
Clinch Dr (gravel)	1106 x 9	125		
Covington Rd *	1791 x 10	162		
* Replace Culvert Pipe				
Tara Ave	489 x 10	43		
Rutherford Dr	2360 x 11	234		
Plaza Dr	380 x 9	37		
TOTAL BID PRICE		601		

Lot 2 (Add Alternate)

ROAD	AVERAGE L x W (FEET)	ESTIMATED TONS	BID PRICE	PRICE PER TON
Ford St (gravel)	888 x 9	98		
Grace St (gravel)	788 x 9	87		
Glenwood St	2745 x 13	329		
TOTAL BID PRICE		514		

Lot 3 (Add Alternate)

ROAD	AVERAGE L x W (FEET)	ESTIMATED TONS	BID PRICE	PRICE PER TON
Hickory Dr (gravel)	1077 x 9	123		
Pepper Loop Rd (gravel)	762 x 9	86		
Pleasant Valley Rd	4261 x 11	432		
Montana Dr	103 x 10	11		
TOTAL BID PRICE		652		

Lot 4 (Add Alternate)

ROAD	AVERAGE L x W (FEET)	ESTIMATED TONS	BID PRICE	PRICE PER TON
Old Home Pl (gravel)	541 x 9	62		
Absher Rd (gravel)	559 x 10	71		
Bug Rd	955 x 11	106		
TOTAL BID PRICE		239		

Lot 5 (Add Alternate)

ROAD	AVERAGE L x W (FEET)	ESTIMATED TONS	BID PRICE	PRICE PER TON
Central Ave & Surface Dr	588 x 19.5	102		
TOTAL BID PRICE		102		