

**Extended Detention Basin and Outlet Pipe and Channel  
Richlands High School, Tazewell County VA**

**Bid Sheet**

ITEM	ITEMS OF WORK	UNIT	QUANTITY	UNIT PRICE	AMOUNT
<b>ACCESS AND STAGING SUBTOTAL</b>					<b>\$ -</b>
1.01	MOBILIZATION	LS	1		-
1.02	CONSTRUCTION STAKEOUT SURVEY	LS	1		-
1.03	STAGING	LS	1		-
<b>EROSION AND SEDIMENT CONTROL SUBTOTAL</b>					<b>\$ -</b>
2.01	STONE CONSTRUCTION ENTRANCE	EA	1		-
2.02	WATER CONTROL (DEWATER PUMP AND FILTER BAG)	EA	1		-
2.03	SILT FENCE	FT	284		-
2.02	LOD/SAFETY/TREE PROTECTION FENCE	FT	1,425		-
2.04	CULVERT INLET PROTECTION	EA	1		-
<b>EXTENDED DETENTION BASIN</b>					<b>\$ -</b>
3.01	EARTHWORKS	CY	817		-
3.02	CLEARING AND GRUBBING	AC	0.29		-
3.03	CUT TO BE HAULED OFF-SITE	CY	784		-
3.04	RISER STRUCTURE W/ ORIFICE	LS	1.00		-
3.05	GABION WALL	CY	4.59		-
3.06	RIPRAP INLET PROTECTION	SY	77.78		-
3.07	UPLAND SEED MIX	AC	0.23		-
3.08	WETLAND SEED MIX	AC	0.10		-
<b>OUTLET PIPE AND OUTLET DITCH</b>					<b>\$ -</b>
4.01	REMOVAL OF EXISTING STOCKPILE AREA	CY	300		-
4.02	24" CPEP OUTLET PIPE (AVAILABLE ON-SITE)	LF	284.50		-
4.03	STORM MANHOLE JUNCTION	EA	1.00		-
4.04	OUTLET PIPE CUT	CY	1,120		-
4.05	TRENCH BOX 6FT LENGTH (4' WIDE x8' DEPTH)	EA	10.00		-
4.06	OUTLET PIPE BACKFILL	CY	1,120		-
4.07	DITCH CLEARING AND GRUBBING	AC	0.24		-
4.08	DITCH EARTHWORKS	CY	68.00		-
4.09	DITCH CUT HAUL OFF	CY	68.00		-
4.10	DITCH RIPRAP PROTECTION	SY	24.44		-
4.11	ABANDONED PIPE PLUG	EA	2.00		-
4.12	UPLAND SEED MIX	AC	0.24		-
<b>SITE DEMOBILIZATION SUBTOTAL</b>					<b>\$ -</b>
5.01	SITE CLEAN UP	LS	1		-
5.02	DEMOBILIZATION	LS	1		-
5.03	AS-BUILT SURVEY	LS	1		-
<b>TTL</b>	<b>TOTAL</b>				<b>\$ -</b>
		<b>CONTINGENCIES - 15%</b>			
		<b>TOTAL</b>			